

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

For corners in

| Kent (County) | Located in: Gaines Township | Corner Code # |
|---------------------------------------|--------------------------------|---------------|
| 1. Public Land Survey | T <u>5N</u> R <u>11W</u> | <u>I-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 AUG -8 AM 8:45
 REG. OF DEEDS
 9294
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Randy Kolehouse, in a field survey on January 27 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|------|------|----------------|--------------------|------------------------------------|
| I-10 | 1831 | G.L.O. Notes | Mullett | Set Post |
| | N/A | Witness Map | K.C. Surveyor | 3/4" Iron |
| | 1974 | L.C.R.C. #642 | Exxel Engineering | 3/4" Iron |
| | 1981 | L.C.R.C. #2310 | Nederveld & Jonker | Fnd. 3/4" Iron / Set K.C. Monument |
| | 1994 | L.C.R.C. #7164 | Glaza & Associates | K.C. Monument |

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/7/96
 CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Nederveld & Jonker on 7/24/81 and was recorded per L.C.R.C. #2310.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-10 Found a Standard Kent County Monument 3' M/L East of the C/L of Hanna Lake Avenue per L.C.R.C.'s #2310 and #7164 as set by Nederveld & Jonker in place of a 3/4" iron they found that checked L.C.R.C. #642 and K.C. Surveyor's records.

| L.C.R.C. #2310 | L.C.R.C. #7164 |
|---|---|
| SE cor. brick planter S 20° W 107.19' | SE corner of brick planter S 20° W 107.19" |
| NE cor. 7' X 15' conc. box N 80° W 32.45' | Nail & K.C. remon. tag in N side P. pole S 65° W 34.26' |
| Nail & K.C. Remon tag N side P. pole S 65° W 34.18' | "X" cut in West end of concrete culvert N 10° W 105.75' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard Kent County Monument
 SE corner of brick planter S 20° W 107.19"
 NE corner 7' x 15' concrete box N 80° W 32.45'
 Nail & K.C. remon. tag in N side P. pole S 65° W 34.26'
 "X" cut in West end of concrete culvert N 10° W 105.75'



Signed by Randy J. Kolehouse Date 7/23/96
 EARTH TECH

Surveyor's Michigan License No. 25854