

SURVEY & REMONUMENTATION

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

<u>Kent</u> (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>I-11</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

9295

96 AUG -8 AM 8:45

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on December 27 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11	1831	G.L.O. Notes	Mullett	Set Post
	1964	Witness Map	K.C. Surveyor	Monument Box
	1974	L.C.R.C. #642	Exxel Engineering	Iron in Mon. Box
	1982	L.C.R.C. #2832	Jonker Land Surveys	Fnd. Iron in Mon. Box / Set K.C. Monument
	1994	L.C.R.C. #7188	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/17/96

CHAIRMAN Harry Huber

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Robert Jonker on 4/15/82 and was recorded per L.C.R.C. #2832.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found a Standard Kent County Monument at the intersection of 100th Street (bit.) running E & W and Hanna Lake Avenue (bit.) running N & S per L.C.R.C.'s #642, #2832 and #7188 as set by Rob Jonker in place of a 3/4" iron in a monument box he found that checked L.C.R.C. #642 and K.C. Surveyor's records.

L.C.R.C. #2832

L.C.R.C. #7188

Remon. tag on SW side p. pole N 30° W 49.10'	K.C. remon tag & nail in SW side P. pole N 30° W 49.10'
Remon. tag on S side p. pole N 70° E 126.8'	K.C. remon tag & nail in S side P. pole N 70° E 126.80'
Remon. tag on E side p. pole S 20° W 91.05'	K.C. remon tag & nail in E side P. pole S 20° W 91.05'
On C/L "X"	Face of concrete R.O.W. marker (at base) S 75° W 120.95'
	Face of concrete R.O.W. marker (at base) S 70° E 122.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Standard Kent County Monument

- Nail & K.C. remon. tag on SW side P. pole N 30° W 49.10'
- Nail & K.C. remon. tag on S side P. pole N 70° E 126.80'
- Nail & K.C. remon. tag on E side P. pole S 20° W 91.05'
- Face of concrete R.O.W. marker (at base) S 75° W 120.95'
- Face of concrete R.O.W. marker (at base) S 70° E 122.23'

Signed by Randy J. Kolehouse
 EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

