

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

9297

Register of Deeds Stamp & File Number

96 AUG -8 AM 8:46

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on December 27 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-13	1817	G.L.O. Notes	L. Lyon	Set Post
	1964	Witness Map	K.C. Surveyor	2" Iron
	1972	L.C.R.C. #337	Williams & Works	1" Iron
	1981	L.C.R.C. #1706	Williams & Works	Fnd. 1" and 3" Iron / Set K.C. Monument
	1994	L.C.R.C. #7167	Glaza & Associates	K.C. Monument

Note: This corner is not common with I-1, T4N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/25/81 and was recorded per L.C.R.C. #1706.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found a Standard Kent County Monument 3' North of the C/L of 108th Street (bit.) running East and West on the C/L of Hanna Lake Avenue (bit.) running North and 53.01' East of I-1, T4N, R11W, per L.C.R.C.'s #1706 and #7167, as set by Williams & Works in place of a 1" iron along side a 3" x 24" iron they found that checked L.C.R.C. #337 and K.C. Surveyor's records.

L.C.R.C. #1706

NW Cor. Garg. (Hse. #10790) Fnd. N 40° E 174.14'  
 SE Cor. Hse. Fnd. (#10790) N 60° E 142.68'  
 C/L Blkt. Rd. (108th) E&W 2.5' ± South  
 C/L Blkt. Rd. (Hanna Lake) North 0.5' ± West  
 Iron West 53.01', Nail East 3.05' & North 3.10'

L.C.R.C. #7167

Nail & K.C. remon tag in N side 14" Ash S 65° W 131.75' (m. 131.64')  
 NW corner of garage foundation, house #10790 N 40° E 174.14' (m. 174.08')  
 SE corner of house foundation #10790 N 60° E 142.68' (m. 142.65')  
 C/L blacktop road (108th) E&W 3' ± South  
 C/L blacktop road (Hanna Lake) North 0.5' ± West  
 Nail & K.C. remon. tag in NW side P. pole N 40° E 64.60' (m. 64.52')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Standard Kent County Monument

Nail & K.C. remon. tag on NW side P. pole N 40° E 64.52'  
 Nail & K.C. remon. tag on N side 14" Ash S 65° W 131.64'  
 SE cor. of hse. fndn. #10790 N 60° E 142.65'  
 NW cor. garage fndn. #10790 N 40° E 174.08'  
 Capped iron in monument box I-1, T4N, R11W, West 53.01'

Signed by Randy J. Kolehouse

Date 7/23/96

Surveyor's Michigan License No. 25854

