

\$7.00
\$2.00

JAN 28 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>J-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REG. OF DEEDS

Lucy Bond

95 DEC 28 PM 2:21

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8915

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on May 12 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-2 This corner was not originally set by the G.L.O.

1960	Survey Records	Williams & Works	Held Intersection of 1/4 Lines (No Iron Set)
1979	L.C.R.C. #1303	Exxel Engineering	Set Iron at Intersection of 1/4 Lines

Note: No record of corner on K.C. Witness Map.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/26/95

CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-2 Found a 1/2" rebar as set by Exxel Engineering in 1979 at fence corner North, East and West per L.C.R.C. #1303. Rebar is within 0.10' of the intersection of 1/4 lines. Accepted rebar as Center Section.

L.C.R.C. #1303

- Spike in side 12" Maple SE 8.90'
- Spike in side 12" Maple West 16.59'
- Spike in side 30" W. Cherry NW 62.32'
- Spike in side 16" Maple NE 43.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-2 Replaced rebar with a Standard 4" x 30" Kent County Monument.

- Spike in side 12" Maple S 45° E 8.90'
- Spike in side 12" Maple S 85° W 16.59'
- Spike in side 30" Cherry Stump N 30° W 62.32'
- Spke in side 16" Maple Stump N 20° E 43.15'
- Nail & K.C. remon. tag in S face 10" Maple N 85° E 17.45'
- P.K. tag in W face 18" Oak N 5° W 56.78'

Signed by *Randy J Kolehouse* Date 12/22/95

EARTH TECH

Surveyor's Michigan License No. 25854

