

**KENT COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
93 DEC 30 PM 2:10

For corners in

<u>Kent</u> (County)	Located In:	Corner Code #
	<u>Gaines Township</u>	
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>J-6</u>
	T _____ R _____	<u>Center of</u>
	T _____ R _____	<u>Section 14</u>
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>Seg 1</u>
	S _____ T _____ R _____	

6864A
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Chris Marschall, in a field survey on December 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-6 Not set by GLO
Set by Exxel at intersection of the 1/4 lines. A 1/2" Iron and Cap was driven through the root of a 6" Elm and is at the same level as the standing water (12' Diameter and up to 6" Deep) in the area.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-6 Found 1/2" Iron with Cap at the intersection of the 1/4 lines. A Kent County Harrison monument was left near this position but was not set due to the seasonal high water table.

SURVEY &
REMONUMENTATION
MAY 16 1997



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-6 1/2" Iron with cap
Nail and Remon tag in SE side of 20" Shagbark Hickory. N 40°E 105.09'
Nail and Remon tag in SE side of 5" Ash S 50°W 35.90'
Nail and Remon tag in SE side of 3" Hickory N 85°E 14.12'
SE corner of small gauge RR Rail Fence Corner Post
Set in a concrete base (at concrete base) N 60°W 7.68'
East and West Fence North 3' ±
North and South Fence West 7' ±

Signed by Chris Marschall Date December 1, 1993
Surveyor's Michigan License No. 18661

SEE OTHER SIDE