

**SURVEY & REMONUMENTATION**

FEB 14 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 AUG -8 AM 8:46  
 REG. OF DEEDS  
*Lucy Sand*  
**9306**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

K-1	1831	G.L.O. Notes	Mullett	Set Post
	1952	Witness Map	K.C. Surveyor	Boat Spike
	1981	L.C.R.C. #2073	Nederveld & Jonker	1-1/2" Iron
	1983	L.C.R.C. #3476	William Byl	Fnd. 1-1/2" Iron in Mon. Box / Set K.C. Monument
	1988	L.C.R.C. #5003	J. Bueche	K.C. Monument
	1993	L.C.R.C. #6763	R. Roon	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN Randy Kolehouse

This corner is not common with K-13 T6N R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 7/25/83 and was recorded per L.C.R.C. #3476.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-1 Found a Standard Kent County Monument on the C/L of 60th Street (bit.) running East & West 27' East of the C/L of East Paris Avenue (bit.) running North and South, 27.05' East of K-13, T6N, R11W, as set by William Byl in place of a 1-1/2" iron in a monument box he found that checked L.C.R.C. #2073 and the G.L.O. distance to K-13, T6N, R11W.

L.C.R.C. #3476

L.C.R.C. #5003

L.C.R.C. #6763

SW cor. Sec. 36, 6-11 (Kent Co. Mon.) W 27.08'

K.C. Mon (K-13, T6N, R11W) West 27.08'

Top Center Fire Hydrant S 10° 86.77' (m. 86.65')  
 Cor. K-13 West 27.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**K-1** Standard Kent County Monument

- C/L top hydrant S 10° E 86.65'
- Nail & K.C. remon. tag on NW side 16" Elm S 57° W 122.08'
- Nail & K.C. remon. tag on SE side Light pole N 10° W 27.16'
- Nail & K.C. remon. tag on N side 14" Hickory S 80° E 143.91'
- K.C. Mon. at K-13, T6N, R11W, West 27.05'

Signed by Randy J. Kolehouse  
 EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

