

SURVEY & REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

For corners in Kent **COMMISSION**
 (County)

Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 AUG -8 AM 8:46
 REG. OF DEEDS
 9309

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 17 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1	0	12				
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4	1831	G.L.O. Notes	Mullett	Set Post
	1977	L.C.R.C. #1029	Exxel Engineering	1" Iron at Fence Corner
	1982	L.C.R.C. #2836	Jonker	Fnd. 1" Iron at Fence Corner / Set K.C. Monument
	1994	L.C.R.C. #7160	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/7/96
 CHAIRMAN Stan Hubers

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by R. Jonker on 4/28/82 and was recorded per L.C.R.C. #2836.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found a Standard Kent County Monument at the corner of woods running North and West on field division line running East per L.C.R.C.'s #1029, #2836 and #7160 as set by Rob Jonker in place of a 1" iron at an old fence corner he found that checked L.C.R.C. #1029.

L.C.R.C. #2836

L.C.R.C. #7160

Remon. tag on NE side 24" Oak N 25° W 29.35'
 Remon. tag on N side 24" Ash N 85° W 24.52'
 Remon tag on NE side 6" Hickory N 40° W 53.90'
 Remon tag on E side 36" Oak N 05° W 49.37'
 At SE corner of woods
 At fence corner to N & W
 On field line to East

Remon. tag on NE side 24" Oak N 25° W 29.35'
 Remon. tag on N side 24" Ash N 85° W 24.52'
 Remon tag on NE side 6" Maple N 40° W 53.90'
 At SE corner of woods
 On field line to East
 K.C. remon tag & nail in W'y side P. pole S 30° E 114.04'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Standard Kent County Monument

Nail & K.C. remon. tag on NE side 24" Oak (stump) N 25° W 29.35'
 Nail & K.C. remon. tag on N side 24" Ash (stump) N 85° W 24.52'
 Nail & K.C. remon. tag on NE side 6" Maple N 40° W 53.90'
 Nail & K.C. remon. tag on W' side P. pole S 30° E 114.04'

Signed by Randy J. Kolehouse

Date 7/23/96



Surveyor's Michigan License No. 25854