

SURVEY & REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

COMMISSION

Kent (County)	Located in: Gains Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

96 AUG -8 AM 8:47

REG. OF DEEDS
Luis St. Bond
9313

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on December 27 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	18		20		21		22		23		24		
9													
10	20		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1831	G.L.O. Notes	Mullett	Set Post
	N/A	Witness Map	K.C. Surveyor	PK Nail in B.T.
	1974	L.C.R.C. #849	Medema, Van Kooten & Assoc.	Fnd. PK / Set "T" Iron
	1981	L.C.R.C. #2297	Nederveld & Assoc.	Ffound "T" Iron / Set K.C. Monument
	1984	L.C.R.C. #7161	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 2/6/96

CHAIRMAN Randy Kolehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Nederveld & Assoc. on 7/24/81 and was recorded per L.C.R.C. #2297.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found a Standard Kent County Monument 0.5' West of C/L of East Paris Avenue (bit.) on line of a brush line running West per L.C.R.C.'s #2297 and #7161 as set by Nederveld & Associates in place of a "T" iron which checked L.C.R.C. #849 and K.C. Surveyor's records.

L.C.R.C. #2297

L.C.R.C. #7161

"X" on top E end 15" conc. culv. N 65° E 25.83'
 Nail & K.C. Remon. tag N side M.B.T. pole N 90° W 27.74'
 Nail & K.C. Remon. tag NE side 14" Willow N 25° W 103.38'
 Nail & K.C. Remon. tag W side 30" Maple S 10° E 173.63'
 NE cor. hse. fnd. N 40° W 96.0'

"X" on top East end 15" conc. culv. N 65° E 25.94'
 Nail & K.C. Remon. tag in N side M.B.T. pole N 90° W 27.65'
 Nail & K.C. Remon. tag in NE side 30" Willow N 25° W 103.00'
 Nail & K.C. Remon. tag in W side 36" Maple S 10° E 173.32'
 NE corner house foundation N 40° W 96.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Standard Kent County Monument

"X" on top East end 15" conc. culv. N 65° E 25.94'
 Nail & K.C. Remon. tag in N side M.B.T. pole N 90° W 27.65'
 Nail & K.C. Remon. tag in NE side 30" Willow N 25° W 103.00'
 Nail & K.C. Remon. tag in W side 36" Maple S 10° E 173.32'
 NE corner house foundation N 40° W 96.05'

Signed by Randy J. Kolehouse

Date 7/23/96

Surveyor's Michigan License No. 25854

