

**SURVEY &
REMONUMENTATION**

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in **COMMISSION**

Kent (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>K-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	_____
	S _____	T _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____	_____
	S _____	T _____	_____

REG. OF DEEDS

9318

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 AUG -8 AM 8:17

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Randy Kolehouse in a field survey on January 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1817	G.L.O. Notes	L. Lyon	Set Post	P.A. 345 1990 KENT COUNTY
	1927	Witness Map	K.C. Surveyor	Large Stone	PEER APPROVED 3/27/96
	1975	L.C.R.C. #958	McPherson	1/2" Re-rod	CHAIRMAN <u>Randy Kolehouse</u>
	1981	L.C.R.C. #1703	Williams & Works	Fnd. 1/2" Re-rod / Set K.C. Monument	
	1983	L.C.R.C. #4428	R. Jonker	Fnd. Stone / Set K.C. Monument	

Note: This corner is not common with K-1, T4N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/25/81 and was recorded per L.C.R.C. #1703, and by Rob Jonker on 4/12/83 and recorded per L.C.R.C. #4428.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found a Standard Kent County Monument at the C/L intersection of 108th Street running East and West and East Paris Avenue running North per L.C.R.C.'s #4428 and 7176 as set by Rob Jonker in place of a stone he found that checked K.C.R.C. Road Plans.

L.C.R.C. #1703

L.C.R.C. #4428

Nail & K.C. Remon. Tag in N. Side 3" Ash S 72° E 100.79'

Set 4" std. K.C. monument over pointed stone
Remon. tag on E. side p. pole N 40° W 84.85'
Remon. tag on E. side p. pole N 30° E 68.32' (m. 68.25')
U.S.G.S. B.M. S 15° W 65.00'
Cast iron mon. East 14.3'

Note: Monument set in L.C.R.C. #1703 appears to be K-1, T4N, R11W.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument

Nail & K.C. remon. tag on E. side P. pole N 40° W 84.85'
Nail & K.C. remon. tag on E. side P. pole N 30° E 68.25'
U.S.G.S. B.M. S 15° W 65.00'
Cast iron mon. East 14.30'

Signed by Randy J. Kolehouse
EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854

