

SURVEY &
REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

COMMISSION

For corners in

Kent (County)	Located in: Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS

9319

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 AUG -8 AM 8:47

Randy Kolehouse, in a field survey on January 3 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 This corner was not originally set by the G.L.O.

1975	L.C.R.C. #898	Exxel Engineering	"T" Iron
1983	L.C.R.C. #3477	William Byl	Found "T" Iron / Set K.C. Monument
1989	L.C.R.C. #4964	J. Bueche	K.C. Monument
1993	L.C.R.C. #6763	R.L. Roon	K.C. Monument

Note: This corner is not common with L-13, T6N, R11W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 7/21/83 and was recorded per L.C.R.C. #3477.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found a Standard Kent County Monument on C/L of 60th Street (bit.) running East and West per L.C.R.C.'s #4964 and #6763 as set by William Byl in place of a "T" iron he found which checked L.C.R.C. #898.

L.C.R.C. #4964

Nail & Remon Tag E side 22" quad Maple S 40° W 32.13'
Nail & Remon Tag N side 21" Oak S 80° W 79.52' (m. 79.48')
Nail & Remon Tag S side 8" Ash clump N 70° W 67.45'
Nail & Remon Tag E side p. Pole N 15° W 62.80'
K.C. Mon (L-13, T6N, R11W) West 13.57'

L.C.R.C. #6763

Cor. L-13 West 13.55' (m. 13.54')
Nail & Tag in 18" Ash Clump N 70° W 67.44' (m. 67.42')
Nail & Tag in P. pole N 15° W 62.85' (m. 62.84')
Nail & Tag in 22" Quad Maple S 40° W 32.09' (m. 32.04')
Nail & Tag in 9" Ash S 60° W 40.80' (m. 40.78')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument

Nail & K.C. remon. tag on E side P. pole N 15° W 62.85'
Nail & K.C. remon. tag on SW side 4" Oak S 25° E 31.08'
Nail & K.C. remon. tag on E side 22" Maple (Quad) S 40° W 32.04'
Nail & K.C. remon. tag on E side 9" Ash S 60° W 40.78'
Nail & K.C. remon. tag on N side 21" Oak S 80° W 79.48'
Nail & K.C. remon. tag on S side 18" Ash (Clump) N 70° W 67.42'
K.C. Mon S 1/4 36, T6N, R11W, West 13.54'

Signed by Randy J. Kolehouse

Date 7/23/96

EARTH TECH

Surveyor's Michigan License No. 25854

