

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11W</u>	<u>L-3</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 AUG - 8 AM 8:47  
 REG. OF DEEDS  
*[Signature]*

**9320**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3	1831	G.L.O. Notes	Mullett	Set Post
	1962	Witness Map	K.C. Surveyor	3/4" Iron in Mon. Box
	1975	L.C.R.C. #827	Exxel Engineering	3/4" Rod in Mon. Box
	1975	L.C.R.C. #848	Medema, Van Kooten & Assoc.	Solid Iron in Mon. Box
	1981	L.C.R.C. #2287	Nederveld & Associates	Fnd. 5/8" Solid Iron in Mon. Box / Set K.C. Monument
	1994	L.C.R.C. #7159	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN [Signature]

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Nederveld & Associates on 8/17/81 and was recorded per L.C.R.C. #2287.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found a Standard Kent County Monument in a monument box on the C/L of 68th Street (bit.) running East and West on a line of tree row running North & South per L.C.R.C.'s #827, #2287 and #7159 as set by Nederveld & Associates in place of a 5/8" solid iron rod in a monument box they found that checked L.C.R.C.'s #827, #848 and K.C. Surveyor's records.

L.C.R.C. #2287

L.C.R.C. #7159

Nail & K.C. Remon. tag S side P. pole N 83° E 111.80'  
 Nail & K.C. Remon. tag N side T. pole S 68° E 131.46'  
 Nail & K.C. Remon. tag NW side T. pole S 50° W 47.40'  
 "X" top S end conc. culvert S 10° E 26.03'


Nail & K.C. remon. tag in S side P. pole N 83° E 111.80'  
 Nail & K.C. remon. tag in N side T. pole S 68° E 131.46'  
 Nail & K.C. remon. tag in NW side T. pole S 50° W 47.40'  
 "X" top S end conc. culvert S 10° E 26.03'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Standard Kent County Monument in a Monument Box

Nail & K.C. remon. tag on S side P. pole N 83° E 111.80'  
 Nail & K.C. remon. tag on N side T. pole S 68° E 131.46'  
 Nail & K.C. remon. tag on NW side T. pole S 50° W 47.40'  
 "X" top S end conc. culvert S 10° E 26.03'



Signed by Randy J. Kolehouse  
 EARTH TECH

Date 7/23/96

Surveyor's Michigan License No. 25854