

\$7.00
\$2.00

JAN 23 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

COMMISSION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>L-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 28 PM 2:22
REG. OF DEEDS
8022
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	6	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on _____ 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-6 This corner was not originally set by the G.L.O.


1957 Survey Notes Williams & Works Fence Corner on True N-S 1/4 Line
1963 Wit. Map K.C. Surveyor Steel Fence Post

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/26/95
CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-6 Found "T" fence post as called for in Williams & Works survey records from 1963. Fence post is on the N-S 1/4 line and 6' South of the E-W 1/4 line fence. Accepted "T" fence post as the Center of Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-6 Set a Standard 4" x 30" Kent County Monument.

- Nail & K.C. remon. tag in S face P. pole N 80° W 70.21'
- Nail & K.C. remon. tag in NW face 12" Cherry N 55° E 22.63'
- Nail & K.C. remon. tag in NE face 10" Ash S 05° E 1.58'
- Nail & K.C. remon. tag in E face 4" Hawthorn N 10° W 14.15'



Signed by Randy J. Kolehouse Date 12/22/95
EARTH TECH

Surveyor's Michigan License No. 25854