

**SURVEY & REMONUMENTATION**

FEB 14 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

| Kent<br>(County)                   | Located in: | Gaines<br>Township | Corner Code # |
|------------------------------------|-------------|--------------------|---------------|
| 1. Public Land Survey              | T <u>5N</u> | R <u>11W</u>       | <u>L-11</u>   |
|                                    | T _____     | R _____            | _____         |
|                                    | T _____     | R _____            | _____         |
|                                    | T _____     | R _____            | _____         |
| 2. Property Controlling in Section | S _____     | T _____            | R _____       |
|                                    | S _____     | T _____            | R _____       |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____            | R _____       |
|                                    | S _____     | T _____            | R _____       |

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

96 AUG -8 AM 8:47

REG. OF DEEDS  
*Randy Kolehose*  
 9324

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehose, in a field survey on December 28 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

|      |      |                |                     |   |                           |
|------|------|----------------|---------------------|---|---------------------------|
| L-11 | 1831 | G.L.O. Notes   | Mullett             | Set Post  | P.A. 345 1990 KENT COUNTY |
|      | 1952 | Witness Map    | K.C. Surveyor       | Monument Box                                    | APPROVED 3/7/96           |
|      | 1976 | L.C.R.C. #958  | McPherson           | 3/4" Iron in Monument Box                       | <i>Randy Kolehose</i>     |
|      | 1982 | L.C.R.C. #2842 | Jonker Land Surveys | Found 3/4" Iron in Mon. Box / Set K.C. Monument |                           |
|      | 1994 | L.C.R.C. #7181 | Glaza & Associates  | K.C. Monument in Monument Box                   |                           |

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 4/15/82 and was recorded per L.C.R.C. #2842.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found a Standard Kent County Monument 0.5" North of the C/L of 100th Street on line of a tree row running South as set by Rob Jonker in place of 3/4" iron in monument box he found which checked L.C.R.C. #958 and K.C. Surveyor's records.


| L.C.R.C. #2842                                  | L.C.R.C. #7181                                  |
|---|---|
| Remon. tag on NE side p. pole S 50° E 89.40'    | Remon. tag on NE side p. pole S 50° E 89.40'    |
| Remon. tag on E side p. pole N 05° W 54.27'     | Remon. tag on E side p. pole N 05° W 54.27'     |
| Remon. tag on S side 30" Hickory N 80° W 193.6' | Remon. tag on S side 30" Hickory N 80° W 193.6' |
| SE cor. hse. fnd. N 15° W 89.94'                | SE cor. hse. fnd. N 15° W 89.94'                |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument

Nail & K.C. remon. tag on NE side P. pole S 50° E 89.40'  
 Nail & K.C. remon. tag on E side P. pole N 05° W 54.30'  
 Nail & K.C. remon. tag on S side 30" Hickory N 80° W 193.60'  
 SE cor. hse. fndn. N 15° W 89.94'



Signed by *Randy J. Kolehose* Date 7/23/96  
 EARTH TECH

Surveyor's Michigan License No. 25854