

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC -5 AM 9:01

For corners in
KENT COUNTY

(County)	Located In:	Corner Code -#
1. Public Land Survey	T 6N R 11W	M-13
	T 6N R 10W	A-13
	T 5N R 11W	M-1
	T 5N R 10W	A-1
2. Property Controlling in Section	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	

Lucy J. Bond
REG. OF DEEDS

7718

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13	1831	GLO	Mullett	Set Post
	1954	Kent Co. Wit.		Iron
	1975	LCRC #898	Bonnema	1/2" Iron
	1982	LCRC #3182	Jonker	Set Kent County Monument
	1989	LCRC #4991	Bueche	Kent County Monument
	1993	LCRC #6757	Roon	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/1/94
CHAIRMAN *Harry Spikes*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11/23/82 and was recorded per LCRC #3182

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" x 24" Iron he found over a 1 1/2" Iron 27" deep. Both Irons check with Kent Co. Wit. and LCRC #898.

LCRC #3182	LCRC #6757
Chisled "X" W. end culv. S15°W 99.24'	Nail & tag P. Pole S55°W 35.30'
Chisled "X" N. end culv. N60°W 43.75'	Nail & tag Guy Pole S25°E 68.66'
Remon. tag T. Pole S50°W 34.97'	Nail & tag P. Pole S50°E 50.83'
Remon. tag P. Pole N60°E 48.52'	Nail & tag P. Pole N60°E 48.65'
NW cor. hse. fnd. S30°E 159.36'	
C/L "X" pavt. is 2' W. m/l	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Standard Kent County Monument	
Nail & KC Remon. tag SE Side P. Pole	S55°W 35.30'
New Nail & KC Remon. tag E. side Guy Pole	S25°E 68.64'
New Nail & KC Remon. tag SW side P. Pole	S50°E 50.81'
Nail & KC Remon. tag SE side P. Pole	N60°E 48.65'
NW cor. hse. fnd.	S30°E 159.36'

Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11/27/94

