

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

COMMISSION

Kent (County)	Located in: Galnes Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 AUG - 8 AM 8:48

REG. OF DEEDS  
*Lucy Bond*

9331

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on January 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6	1817	G.L.O. Notes	L. Lyon	Set Post
	1964	Witness Map	K.C. Surveyor	Concrete Monument
	1983	L.C.R.C. #3580	William Byl	Fnd. Conc. Mon. / Set K.C. Monument
	1991	L.C.R.C. #5987	William Byl	K.C. Monument
	1993	L.C.R.C. #7192	Glaza & Associates	K.C. Monument

Note: This corner is not common with A-6, T5N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 8/29/83 and was recorded per L.C.R.C. #3580.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found a Standard Kent County Monument on C/L of Patterson Avenue at fence line to West 30' North of fence line to East per L.C.R.C.'s #3580, #5987, and #7192 as set by William Byl in place of a concrete monument he found which checked the K.C. Surveyor's records.

L.C.R.C. #3580	L.C.R.C. #5987	L.C.R.C. #7192
Nail & tag, S sd. 15" Hickory N 90 W 50.82'	Nail & tag, S sd. 15" Hickory N 90 W 50.82'	Nail & K.C. remon tag in South side 18" Hickory N 90° W 50.82'
Nail & tag, S sd. 8" Red Pine S 60 W 63.30'	Nail & tag, S sd. 8" Red Pine S 60 W 63.30'	Nail & K.C. remon tag in South side 14" Red Pine S 60° W 63.35' (m. 63.34')
Nail & tag, E sd. 18" Twin Hickory S 30 E 72.15'	Nail & tag, E sd. 18" Twin Hickory S 30 E 72.15'	Nail & K.C. remon tag in East side 12" Twin Oak S 30° E 72.15' (m. 72.14')
C/L USGS monument (Azimuth mark) S 65 E 29.03'	C/L USGS monument (Azimuth mark) S 65 E 29.03'	C/L USGS Monument (azimuth mark) S 65° E S 65° E 29.03' (m. 29.00')
W 1/4 cor. Sec. 18, 5-10, (Kent County Monument) S 00 W 27.82'	W 1/4 cor. Sec. 18, 5-10, (Kent County Monument) S 00 W 27.82'	West 1/4 corner, Sec 18, 5-10 (Kent County Monument) S 00° W 27.82'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument	Nail & K.C. remon. tag on N side 12" Spruce S 45° W 56.73'	Nail & K.C. remon. tag on E side 12" Twin Oak S 30° E 72.14'
	Nail & K.C. remon. tag on NE side 20" Maple S 83° W 24.44'	C/L USGS Mon. (Az. Mrk.) S 65° E 29.00'
	Nail & K.C. remon. tag on S side 14" Red Pine S 60° W 63.35'	K.C. Mon. W 1/4 Sec. 8, T5N, R10W, S 00° W 27.82'
	Nail & K.C. remon. tag on S side 18" Hickory N 90° W 50.82'	

Signed by *Randy J Kolehouse* Date 7/23/96  
EARTH TECH

Surveyor's Michigan License No. 25854

