

FEB 14 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Table with columns: Kent (County), Located in: Gains Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

REG. OF DEEDS

9334

Register of Deeds Stamp & File Number

95 AUG -8 AM 8:48

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on January 5 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: M-9, Date, Description, Name, Monument Type. Includes entries for 1817, 1966, 1976, 1981, 1991, 1994.

Note: This corner is not common with A-9, T5N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Rob Jonker on 9/21/81 and was recorded per L.C.R.C. #2154.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96

Handwritten signature: Harry Hubert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found a Standard Kent County Monument 28.65' North of A-9, T5N, R10W, 4' East of the C/L of Patterson Avenue (bit.) running N-S on line of center of 92nd Street (bit.) running West per L.C.R.C.'s #2154, #5990 and #7193 as set by Rob Jonker in place of a 1/2" iron he found that checked L.C.R.C. #959 and distance North of A-9, T5N, R10W.

L.C.R.C. #2154

L.C.R.C. #5990

L.C.R.C. #7193

Table with 3 columns: L.C.R.C. #2154, L.C.R.C. #5990, L.C.R.C. #7193. Rows describe monument details like 'Remon. tag on S side p. pole N 65° E 62.95'', 'KC Remon. tag & nail S. side (3' higher) P. Pole', etc.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Kent County Monument

- Nail & K.C. remon. tag on E side 4' P. pole S 15° W 154.10'
Nail & K.C. remon. tag on SE side Guy pole S 50° W 60.82'
Nail & K.C. remon. tag on NE side 10" Elm 55° W 78.52'
Nail & K.C. remon. tag on S side 3' High P. pole N 65° E 62.91'
K.C. Mon. NW cor. 30, T5N, R10W, S 00° W 28.65'

Signed by Randy J. Kolehouse, Earth Tech, Surveyor's Michigan License No. 25854

Date 7/23/96

