

**SURVEY & REMONUMENTATION**

MAY 28 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in:	Gaines Township	Corner Code #
Public Land Survey	T 5N	R 11W	A-1
	T	R	
	T	R	
	T	R	
Property Controlling in Section	S	T	Seg. 2
Miscellaneous Property in Sec.	S	T	
	S	T	

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 AUG -8 AM 8:29  
 REG. OF DEEDS  
*Lucy Bond*  
**9201**  
 Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randy Kolehouse, in a field survey on June 21 19 96, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

Date	Description	Surveyor	Monument
1817	G.L.O. Notes	L. Lyon	Set Post
1961	Wit. Map	K.C. Surveyor	Iron
1975	L.C.R.C. #908	Exxel Engineering	1/2" Iron in Mon. Box
1981	L.C.R.C. #1684	Williams & Works	Fnd. Mon. Box / Set K.C. Mon.
1988	L.C.R.C. #4726	Bueche	K.C. Monument
1994	L.C.R.C. #7719	Earth Tech	Reset K.C. Monument

Note: This corner is common with A-13, T6N, R11W; M-13, T6N, R12W; and M-1, T5N, R12W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/16/81 and was recorded per L.C.R.C. #1684.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This monument was reset using Williams and Works survey records and plats (see L.C.R.C. #7719) but after further review by the Kent County Surveyors Peer Group it was decided to move this corner 0.38' West and 0.25' South to check location of P.K. nail which better checks the location of this corner being used by most Kent County Surveyors.

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/21/96  
 CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Kent County Monument

- SW cor. bldg. (brick) N 48° E 97.34'
- SE cor. brick fndn. N 66° W 82.06'
- C/L hyd. N 34° E 76.86'
- Nail & K.C. remon. tag in NE side P. pole S 71° E 105.90'
- P.K. Nail & K.C. remon. tag in NE side T. pole S 60° E 58.85'
- P.K. Nail & K.C. remon. tag in SE side G. pole N 58° E 59.30'
- Nail & K.C. remon. tag in SE side P. pole S 55° W 63.35'



By *Randy J. Kolehouse* Date 7/23/96  
 EARTH TECH

Surveyor's Michigan License No. 25854