

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 6 N. R. 9 W.	K-9, L-9, L-11, M-9
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Q: 1-29-74
P: 1-21-74

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, F. E. Spicer do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on January 17, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-9 - Stone	L-11 - 1/2" Iron	M-9 - 1" Iron
12" Walnut SW 83.7'	36" Osage orange N 28.52'	12" Walnut SW 48.4'
24" Walnut NW 91.4'	SE cor N hdwl WNW 33.62'	24" Walnut NW 41.6'
14" Walnut NE 83.4'	12" Elm SSE 45.96'	24" Walnut NE 53.6'

NE cor 25

L-9 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-9 - Set conc nail in \odot joint E&W rd using prorated of MSHD meas between N 1/4 Sec #26 and NE Sec #25
- L-9 - Set conc nail \odot joint E&W rd and midway between NW cor Sec #25 and NE cor Sec #25
- L-11 - Found 3/4" iron in mon box one-half mile E of Pratt Lake Ave.
- M-9 - Found 1" solid iron by wit

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 - Conc nail	L-9 - Conc nail	M-9 - 1" Solid iron
24" Walnut S70°W 83.58'	SE cor hdwall N30°W 37.80'	38" Walnut N61°E 54.83'
16" Walnut N20°E 73.68'	NE cor hdwall S40°W 36.90'	CP/MBT pole N10°E 53.10'
30" Walnut N25°W 92.00'	14" Oak S30°E 42.22'	32" Walnut N46°W 42.35'
Centerline E & W rd	Centerline E & W rd	CP/MBT pole S30°W 57.40'
<u>L-11 - 3/4" Iron in mon box</u>		
+ cut SE end culv S55°W 37.35'		
+ cut NE end culv N50°W 38.73'		
Wood fence post N00°E 33.88'		
2' S of centerline of E & W rd		

SIGNED BY F. E. Spicer DATE 1/28/74
 SURVEYOR'S MICHIGAN REGISTRATION NO. 7877

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR

