

Kent Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>25</u> T. <u>6</u> N. R. <u>9</u> W.		<u>M-10, K-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on _____, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>M-10 Set 1" pipe w/aluminum cap at G.L.O. distance from W 1/4 Cor. Sec. 30, T6N, R8W</p> <p>No previous Witnesses</p>	<p>K-10 Set 1" pipe w/aluminum cap midway and on line between N-S Section corners.</p> <p>No previous witnesses.</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>M-10 E 1/4 Cor. Sec. 25 1" pipe w/aluminum cap S58°E, 22.72', 7" Cottonwood, spike & tag S2°E, 81.16', 13" Ash, spike & tag S70°W, 98.10', Telegraph pole, spike & tag West, 47.26', E. edge E. rail</p>	<p>K-10 W 1/4 Cor. Sec. 25 S43°E, 5.53', 6" W. Ash N61°E, 15.62', 9" Soft Maple N63°W, 10.33', 5" W. Ash S53°W, 19.68', 6" Elm</p>
---	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

DATE 5-8-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

