

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:50
REG. OF DEEDS
[Signature]

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T6N R 9W	A-6
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

9024

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Date	Monument	Accessories	Restoration
A-6 1830	GLO	Mullett	Not Set
1938	Kent Co. Wit.		Conc. Monument
1977	LCRC #1016	McCombs	1" Pipe
1987	LCRC #4543	Meyer	1 1/2" Iron
1988	LCRC #4901	Chettleburgh	Set Kent County Monument
1991	LCRC #6107	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/2/96
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 4/16/88 and was recorded per LCRC #4901

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh in place of the 1" Pipe in Conc. Monument he found. Said Iron in Monument checks with Kent Co. Wit. and LCRC's #1016, #4543.

LCRC #4901
Nail/tag 21" Hickory S13°E 92.51' Nail/tag 19" Hickory S86°E 39.10' witnesses the same ± as LCRC #4901
Nail/tag 26" Walnut N17°W 75.72'
Nail/tag 34" Oak N88°W 59.90' KC Mon. (M-6, 6-10) South 25.75'
Nail/tag 27" Spruce N35°E 65.80'
Nail/tag 25" Spruce N55°E 43.45'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Standard Kent County Monument

Nail & KC Remon. tag W. side	30" Walnut	N18°W	75.67'
Nail & KC Remon. tag W. side	26" Hickory	S12°E	92.66'
Nail & KC Remon. tag S. side	40" Oak	N88°W	59.95'
Nail & KC Remon. tag NW side	30" Spruce	N35°E	65.75'
Nail & KC Remon. tag NW side	28" Spruce	N55°E	43.44'
Nail & KC Remon. tag N. side	24" Hickory	S87°E	39.11'
Kent County Monument (M-6, T6N, R10)	South		25.76'



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 3/2/96