

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 9W	A-7
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:50

REG. OF DEEDS

Lucy Bond

9025

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Feb. 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7	1830	GLO	Mullett	Set Post
	1965	Kent Co. Wit.		Mon. Box
	1977	LCRC #1016	McCombs	3/4" Iron in Mon. Box
	1988	LCRC #4900	Chettleburgh	Set Kent County Monument
	1991	LCRC #6108	Unema	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 4/11/88 and was recorded per LCRC #4900

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh on Twp. Line in place of the Iron Pipe in he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #1016

<u>LCRC #4900</u>	Nail/tag 20" Oak	N14°W 100.40'	Nail/tag P. Pole	witnesses the same ±
	Nail/tag 24" Willow	N66°W 44.47'	S27°E 79.04'	as LCRC #4900.
	Nail/tag 11" Oak	N84°E 92.54'	KC Mon. (M-7, 6-10)	
	Nail/tag 32" Maple	S68°E 116.22'	South 23.68'	
	Nail/tag 41" Maple	S58°E 76.02'	Mon. Box East 1.76'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

A-7 Standard Kent County Monument

Nail & KC Remon. tag	E. side	22" Oak	N14°W	100.44'
New Nail & KC Remon. tag	S. side	42" Willow	N66°W	44.46'
Nail & KC Remon. tag	S. side	14" Maple	N83°E	92.57'
Nail & KC Remon. tag	N. side	42" Maple	S57°E	76.08'
Nail & KC Remon. tag	N. side	36" Maple	S68°E	116.25'
Nail & KC Remon. tag	SW side	P. Pole	S27°E	78.78'
Kent Co. Mon. (M-7, T6N, R10W)			South	23.69'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/2/96