

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 9W B-3

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:20
REG. OF DEEDS
Luigi Spad

9793

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	•												
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on Jan. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-3	1830	GLO	Mullett	Set Post
	1971	LCRC #103	Chambers	1" Iron
	1981	LCRC #2715	Merdzinski	Set Kent County Monument
	1995	LCRC #8169	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12/30/81 and was recorded per LCRC #2715

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found. Said 1" Iron checks with LCRC #103.

<u>LCRC #2715</u>		<u>LCRC #8169</u>	
18" Oak N70°W	14.27'	C/L steel fc. post	22" Oak N70°W 15.00'
18" Oak N40°E	15.63'	S70°E 0.50'	24" Oak N40°W 15.62'
10" Oak S70°E	17.63'		18" Oak S70°E 17.66'
12" Oak S10°E	33.50'	Cor. on remains of	14" Pine S70°W 32.40'
8" Pine S70°W	32.38'	fence E-W & S	Tw. 14" Oak S10°E 43.28'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3	Standard Kent County Monument		
	Nail & KC Remon. tag NE side	22" Oak	N70°W 15.00'
	Nail & KC Remon. tag NW side	24" Oak	N40°E 15.62'
	Nail & KC Remon. tag NE side	18" Oak	S70°E 17.66'
	Nail & KC Remon. tag N. side	14" Pine	S70°W 32.40'
	Nail & KC Remon. tag E. side	Tw. 14" Oak	S10°E 43.28'
	Centerline of 3" dia. steel fence post		S70°E 0.50'
	Corner is in remains of East, West and South fences		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry J. Huber*