

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 9W	B-6
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on July 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-6 1830---GLO---Not Set
- 1903---Williams & Works---Fence Corner
- 1956---Williams & Works---Fence Corner
- Kent Co. Wits.---No information
- 1976---Survey---Consumers Power Co.---Intersection of 1/4 lines

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/24/97
CHAIRMAN Harry Tubers

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-6 Found Capped Rerod (Nederveld) less than 0.1' S. and less than 0.1' W. of intersection of 1/4 lines. Also found Capped Rerod (CP Co.) 2.9' N. and 0.8' E. of intersection of 1/4 lines. CP Co. survey information fits intersection 1/4 lines ±, but CP Co. Iron is set incorrectly. Fence Corner for fences N-S & E-W is 5' East and 3' North.

The Capped Rerod (Nederveld) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-6 Set Standard Kent Co. Monument (Harrison) in place of the Capped Rerod (Nederveld)
- Nail & KC Remon. tag W. side Tri. 8"-20" Basswood N40°E 41.17'
- Nail & KC Remon. tag N. side 40" Oak S60°E 7.26'
- Nail & KC Remon. tag S. side 14" Basswood N75°W 30.46'
- Nail & KC Remon. tag W. side 22" Beech S05°E 24.71'
- CP Co. rerod - North 3.04'

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 14 AM 10:31
REG. OF DEEDS
Barry Tubers
10059
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 9/25/97

