

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>6N</u> R <u>9W</u> | <u>B-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Mar. 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7	1830	GLO	Mullett	Set Post
	1934	Kent Co. Wit.		Stone
	1977	LCRC #1016	McCombs	Iron
	1982	LCRC #2717	Merdzinski	Set Kent County Monument
	1995	LCRC #8171	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/23/82 and was recorded per LCRC #2717

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Solid Iron he found. Said Solid Iron checks with Kent Co. Wit. and LCRC #1016.

LCRC #2717			LCRC #8171		
Nail & tag 28" Walnut	N10°E	42.23'	Nail & tag 36" Walnut	N10°E	42.19'
Nail & tag 52" Oak	S55°E	43.73'	Nail & tag 60" Oak	S55°E	43.75'
Nail & tag Power Pole	South	63.73'	Nail & tag Power Pole	S00°E	63.73'
Nail & tag 40" Oak	S45°W	34.46'	Nail & tag 50" Oak	S45°W	34.46'
Nail & tag 32" Oak	N50°W	50.61'	Nail & tag 40" Oak	N50°W	50.59'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-7 Standard Kent County Monument
- | | | |
|---|-------|--------|
| Nail & KC Remon. tag E. side 36" Walnut | N10°E | 42.19' |
| Nail & KC Remon. tag NE side 60" Oak | S55°E | 43.75' |
| Nail & KC Remon. tag W. side Power Pole | S00°E | 63.73' |
| Nail & KC Remon. tag NW side 50" Oak | S45°W | 34.46' |
| Nail & KC Remon. tag SW side 40" Oak | N50°W | 50.59' |
- Corner is 1' m/l South of C/L blktp. pav't.; On fence line South
On fence and tree line North

Signed by Kirk Breitels
Surveyor's Michigan License No. 30077


Date 3/27/97

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 APR 29 AM 8:20
 REG. OF DEEDS
Luigi Bondi

9795

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7	●											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN Hannu Hubsch