

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

1. Public Land Survey	T 6N R 9W	B-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

97 OCT 14 AM 10:31

REG. OF DEEDS

Lucy Bond

10061

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on July 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-12 1830---GLO---Not Set
Williams & Works---No information
Kent Co. Wits.---No information
1976---Survey---Consumers Power Co.---Computed Intersection 1/4 lines

No other information found

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97

CHAIRMAN *Harry Tuben*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-12 Established Intersection of 1/4 lines and found extension of fences E-W & S to be approx. 8' E. and 6' S. of this location. Dimensions and angles agree ± with Consumers Power Co. section breakdown.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-12 Set Standard Kent Co. Monument (Harrison) at the Intersection of 1/4 lines

Nail & KC Remon. tag N. side Tw. 12" Hickory	S75°E	46.88'
Nail & KC Remon. tag W. side 27" Hickory	S30°E	9.57'
Nail & KC Remon. tag W. side 20" Hickory	S00°E	32.10
Nail & KC Remon. tag S. side 7" Hickory	N75°W	39.11'
Nail & KC Remon. tag W. side 20" Hickory	N20°E	26.63'

Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 9/22/97

