

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	C-1
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORDING
97 APR 29 AM 8:20
REG. OF DEEDS
Luis J. Bond

9798

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-1	1830	GLO	Mullett	Set Post
	1956	Kent Co. Wit.		3/4" Iron
	1972	LCRC #115	Spicer	3/4" Iron
	1986	LCRC #4463	Rosema	Set Kent County Monument
	1991	LCRC #5810	Unema	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 7/21/86 and was recorded per LCRC #4463

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema on Twp. Line in place of the 1/2" Iron in Mon. Box he found. Said Iron checks with Kent Co. Wit. and LCRC #115.

<u>LCRC #4463</u>	<u>LCRC #5810</u>
Nail & tag 20" Stump S32°W 89.67'	Nail & tag 36" Oak S77°W 98.88'
Nail & tag 30" Oak S77°W 98.90'	Nail & tag 26" Oak N76°W 77.18'
Nail & tag 20" Oak N76°W 77.23'	SE cor. brick house N20°W 76.98'
SE cor. brick house N18°W 76.95'	KC Mon., C-13, 7-9 East 93.69'
C-13, 7-9, KC Mon. East 93.77'	Nail & tag 24" Stump S28°W 68.66'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument			
Nail & KC Remon. tag SE side 36" Oak	S77°W	98.80'	
Nail & KC Remon. tag S. side 28" Oak	N76°W	77.18'	
SE corner brick house	N20°W	76.94'	
Nail & KC Remon. tag N. side 24" Stump	S28°W	68.66'	
Kent Co. Mon., C-13, T7N, R9W	East	93.69'	
C/L N-S bit. road is East 94'±			
C/L E-W bit. road is South 7'±			



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Dubee*