

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:21
REG. OF DEEDS
Lucy Bond

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 9W C-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

9805

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-7	1830	GLO	Mullett	Set Post
	1934	Kent Co. Wit.		Plow Point & Stone
	1977	LCRC #1017	McCombs	3/4" Pipe
	1977	LCRC #1088	VanKooten	1" Iron
	1981	LCRC #2263	Merdinski	Set Kent County Monument
	1995	LCRC #8179	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 6/19/81 and was recorded per LCRC #2263

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron, Plow Point and Stone he found. All check with Kent Co. Wit. and LCRC's #1017 & #1088.

<u>LCRC #2263</u>				<u>LCRC #8179</u>			
Nail & tag P. Pole	S20°E	65.90'		Nail & tag P. Pole	S20°E	65.75'	
Nail & tag 32" Oak	S70°E	124.11'		Nail & tag 42" Oak	S70°E	123.42'	
Nail & tag 12" Oak	N40°W	76.85'		Nail & tag 24" Oak	N40°W	77.02'	
Nail & tag 10" Cherry	North	45.74'		Nail & tag 18" Cherry	N00°E	45.86'	
NW cor. hse. #10416	S45°E	116.72'		NW hse. cor. #10416	S45°E	116.72'	


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Standard Kent County Monument

Nail & KC Remon. tag W. side P. Pole	S20°E	65.75'
Nail & KC Remon. tag N. side 42" Oak	S70°E	123.42'
Nail & KC Remon. tag E. side 24" Oak	N40°W	77.02'
Nail & KC Remon. tag E. side 18" Cherry	N00°E	45.86'
NW cor. hse. #10416	S45°E	116.72'

S. edge of pavement is 1' South; On tree line North



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Fanny Hubert*