

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T6N R9W C-10

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REG. OF DEEDS

Lucy Howard

97 APR 29 AM 8:21

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9808

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-10	1830	GLO	Mullett	Set Post
	1965	Kent Co. Wit.		Mon. Box
	1980	LCRC #1617	VanKooten	Mon. Box
	1981	LCRC #2573	Bueche	Set Kent County Monument
	1995	LCRC #8182	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12/8/81 and was recorded per LCRC #2573

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Rerod he found inside a mon. box. Said Rerod checks with Kent Co. Wit. and LCRC #1617.

LCRC #2573

LCRC #8182

same witnesses as LCRC #2573

NE cor. CB grate	S40°W	19.48'
NW cor. CB grate	S35°E	21.06'
S. edge of steel plate	North	9.23'
PK in top of guard rail post	N60°W	17.95'
PK in top of guard rail post	N65°E	18.06'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 Standard Kent County Monument in mon. box		
NE cor. CB grate	S40°W	19.48'
NW cor. CB grate	S35°E	21.06'
S. edge of steel plate	N00°E	9.23'
Nail & KC Remon. tag top guard rail post	N60°W	17.95'
Nail & KC Remon. tag top guard rail post on C/L blktp. N & S	N65°E	18.04'
C/L E. bound I-96 is North 75' M/L		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345-1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN Harry Hubert

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1985