

MAR 03 1998

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 9W	C-11
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

REG. OF DEEDS

Lucy Bond

97 APR 29 AM 8:21

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9809

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-11	1830	GLO	Mullett	Set Post
	1964	Kent Co. Wit.		Mon. box
	1976	LCRC #940	Merdzinski	1" Iron in mon. box
	1980	LCRC #1404	Merdzinski	1" Iron in mon. box
	1981	LCRC #2262	Merdzinski	Set Kent County Monument in mon. box
	1995	LCRC #8184	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 8/13/81 and was recorded per LCRC #2262

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC's #940 & #1404.

LCRC #2262

LCRC #8184

Nail/tag 36" Pignut	N75°W 130.00'	Nail in curb	Nail/tag 42" Pignut	N75°W 130.06'
Nail/tag P. Pole	N30°W 102.35'	joint	Nail/tag P. Pole	N30°W 102.39'
Nail/tag 36" Catalpa	N15°E 124.18'	N75°E 48.43'	Nail/tag 40" Catalpa	N15°E 124.20'
Nail/tag 28" Oak	S30°E 72.05'		NE cor. base MBT box	S55°W 49.98'
NE cor. conc. base MBT box	S55°W 49.90'		Nail/tag 10" Ash	S40°E 94.96'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument

Nail & KC Remon. tag S. side 44" Pignut	N75°W	129.97'
Nail & KC Remon. tag W. side P. Pole	N30°W	102.39'
Nail & KC Remon. tag W. side 40" Catalpa	N15°E	124.20'
NE cor. to conc. base to MBT box	S55°W	49.98'
Nail & KC Remon. tag NE side 10" Ash	S40°E	94.90'
In C/L intersection of roads N-S, E-W		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN *Harry Kubes*

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995