

MAR 03 1998

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	C-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

Lucy Standa

97 APR 29 AM 8:21

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9810

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-12	1830	GLO	Mullett	Set Post
	1964	Kent Co. Wit.		Iron
	1983	LCRC #3444	McCombs	1" Iron in mon. box
	1983	LCRC #3607	Kolehouse	Set Kent County Monument
	1995	LCRC #8183	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/2/83 and was recorded per LCRC #3607

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found over a 3" Iron in a mon. box. Both Irons check with Kent Co. Wit. and LCRC #3444.

LCRC #3607

LCRC #8183

Nail & tag 26" Oak	N20°E	66.85'	Nail & tag 36" Oak	N20°E	66.80'
Nail & tag 45" Oak	N85°E	24.10'	Nail & tag 52" Oak	N85°E	24.09'
Nail & tag 12" Walnut	N20°W	78.85'	Nail & tag 18" Walnut	N20°W	78.72'
Nail & tag 8" Elm	S55°W	30.90'	Nail & tag 12" Elm	S45°W	37.78'
			Nail & tag 10" Elm	S35°E	54.58'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Standard Kent County Monument

Nail & KC Remon. tag W. side 36" Oak	N20°E	66.80'
Nail & KC Remon. tag S. side 52" Oak	N85°E	24.09'
Nail & KC Remon. tag W. side 18" Walnut	N20°W	78.72'
Nail & KC Remon. tag SE side 12" Elm	S45°W	37.78'
Nail & KC Remon. tag SW side 10" Elm	S35°E	54.58'

In C/L Morse Lake Ave. B.T.
On line of fence running East



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Hubert*