

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located in: Corner Code #

- | | | |
|------------------------------------|-----------|------|
| 1. Public Land Survey | T 6N R 9W | C-13 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

REG. OF DEEDS

Lucy Spauld

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:21

9811

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|------|------|---------------|-----------|--------------------------|
| C-13 | 1830 | GLO | Mullett | Set Post |
| | 1963 | Kent Co. Wit. | | 1" Iron |
| | 1983 | LCRC #3266 | Hay | 1" Iron |
| | 1983 | LCRC #3606 | Kolehouse | Set Kent County Monument |
| | 1995 | LCRC #8185 | Breitels | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 10/29/83 and was recorded per LCRC #3606

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Large Spike he found over a "T" Iron. Both Irons check with Kent Co. Wit. & LCRC #3266.

LCRC #3606

- | | | |
|--------------------------------------|-------|--------|
| Nail & tag P. Pole | S30°W | 18.55' |
| Nail & tag 30" Maple | N40°W | 32.80' |
| NW cor. W. end conc. curb return | N55°E | 29.75' |
| NW cor. conc. pad to MBT box | S55°E | 40.9' |
| Iron at NE cor. Section 6, T5N, R9W. | East | 75.85' |

LCRC #8185


same witnesses as LCRC #3606

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Standard Kent County Monument

- | | | |
|---|-------|--------|
| Nail & KC Remon. tag W. side P. Pole | S30°W | 18.61' |
| Nail & KC Remon. tag E. side 36" Maple | N40°W | 32.80' |
| NW cor. W. end conc. curb return | N55°E | 29.75' |
| NW cor. conc. pad to MBT box | S55°E | 40.89' |
| Kent Co. Mon. at NE cor. Section 6, T5N, R9W. | S90°E | 75.80' |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97
CHAIRMAN *Harvey Hubert*