

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>9W</u>                   | D-5         |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

REG. OF DEEDS

*W. J. Staveland*

97 APR 29 AM 8:21

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9813

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-5	1830	GLO	Mullett	Set Post
	1963	Kent Co. Wit.		Pointed Stone
	1974	LCRC #668	VanKooten	Pointed Stone
	1982	LCRC #2720	Merdzinski	Set Kent County Monument
	1995	LCRC #8187	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/8/82 and was recorded per LCRC #2720

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Pointed Stone he found. Said Pointed Stone checks with Kent Co. Wit. and LCRC #668.

LCRC #2720

Nail & tag 30" Oak	South	43.40'
Nail & tag 20" Oak	East	22.68'
Nail & tag 20" Oak	N45°E	16.95'
Nail & tag 18" Oak	N30°W	17.00'
Nail & tag 10" Maple	N10°E	25.39'

LCRC #8187

Nail & tag 40" Oak	S00°E	44.15'
Nail & tag 26" Oak	S90°E	22.87'
Nail & tag 28" Oak	N45°E	17.45'
Nail & tag 14" Maple	N10°W	25.41'
Nail & tag 4" Ash	S90°W	10.68'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Standard Kent County Monument

Nail & KC Remon. tag E. side 40" Oak	S00°E	44.15'
Nail & KC Remon. tag S. side 26" Oak	S90°E	22.87'
Nail & KC Remon. tag NW side 28" Oak	N45°E	17.45'
Nail & KC Remon. tag E. side 14" Maple	N10°E	25.41'
Nail & KC Remon. tag S. side 4" Ash	S90°W	10.68'

Corner is at remains of fence West and South fence corner



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97  
CHAIRMAN *Henry Habere*