

**KENT COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

93 DEC 20 AM 11:57

For corners in

Kent (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 6N R 9W D-8 _____
 T _____ R _____ Center _____
 T _____ R _____ Section 20 _____
 T _____ R _____ Lowell _____
 2. Property Controlling S _____ T _____ R _____ Township _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

W. J. Bond
REG. OF DEEDS

6853

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Thomas W. Chettleburgh, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W & W 1961, Found and held monument
 monument 0.5' West of N-S 1/4 line
 South 1/4 Corner Section 20 2663.2'
 West 1/4 Corner Section 20 2630.0'

Nederveld and Jonker 1980, Found 1" iron in monument box - record LCRC #1387

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" Concrete Monument - checked witnesses LCRC #1387
 Intersection of 1/4 lines 0.30'S and 0.58'E

Hold Concrete Monument for corner

North 1/4 corner Section 20 (D-7) N00°00'43"W 2640.06'
 East 1/4 corner Section 20 (E-8) S89°33'41"E 2620.94'
 South 1/4 corner Section 20 (D-9) S00°02'13"E 2663.23'
 West 1/4 corner Section 20 (C-8) N89°34'27"W 2629.53'

Replaced concrete monument with 4"X30" Harrison Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4"X30" Harrison Monument

Nail/tag	NE side	Multi 8" Hickory	S60°E	26.97'
Nail/tag	W side	24" Oak	S19°E	59.05'
Nail/tag	SE side	8" Oak	S27°W	65.98'
Nail/tag	SE side	7" Hickory	S40°W	41.88'
Nail/tag	SW side	28" Hickory Stump	N37°W	54.65'



Signed by Thomas W. Chettleburgh Date December 20, 1993
 Surveyor's Michigan License No. 16036