

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	6N	R	9W	D-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

REG. OF DEEDS
97 APR 29 AM 8:21
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9815

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-9	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Bolt in pavement
	1978	LCRC #1190	Merdzinski	Bolt in pavement
	1981	LCRC #2374	Bueche	Set Kent County Monument
	1995	LCRC #8189	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/25/81 and was recorded per LCRC #2374

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" x 24" solid rod he found in the pavement. Said Solid Rod checks with Kent Co. Wit. and LCRC #1190.

<u>LCRC #2374</u>		<u>LCRC #8189</u>	
Tag & nail 34" Oak	S70°W 80.70'	Nail & tag 48" Oak	S70°W 80.70'
Tag & nail 24" W. Cherry	S10°W 30.20'	Nail & tag dbl. 16" Cherry	N55°E 82.88'
Tag & nail dbl. 10" Cherry	N55°E 83.10'	Nail & tag dbl. 20" Oak	S20°W 27.74'
Tag & nail 6" Hickory	N30°E 84.36'	Nail & tag 18" Cherry	N30°W 83.34'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 Standard Kent County Monument

KC Remon. tag & nail (4' high) NW side 48" Oak	S70°W 80.70'
KC Remon. tag & nail NW side double 16" W. Cherry	N55°E 82.88'
KC Remon. tag & nail W. side double 10" Oak	S20°W 27.74'
KC Remon. tag & nail E. side 14" Cherry	N30°W 83.34'
C/L blktp. E & W is North 4.55'±	
C/L gravel North is East 4'±	
On fence & tree row South	



Signed by Kirk Breitels

Date 3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN [Signature]