

**SURVEY & REMONUMENTATION**

MAR 03 1998 KENT COUNTY REMONUMENTATION

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**  
(County)

Located In: Corner Code #

1. Public Land Survey	T 6N R 9W	E-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REG. OF DEEDS

*Lucy Spand*

97 APR 29 AM 8:21

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9820

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-5	1830	GLO	Mullett	Set Post
	1933	Kent Co. Wit.		Iron & Stone
	1973	LCRC #545	Spicer	1/4" Solid Iron
	1981	LCRC #1736	Merdzinski	Set Kent County Monument
	1995	LCRC #8194	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 11/24/80 and was recorded per LCRC #1736

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1 1/4" Iron Pipe over 2-1" Iron Pipes he found surrounded by clay dishes and broken glass. All check with Kent Co. Wit. & LCRC #545.

LCRC #1736

LCRC #8194

Nail & tag 40" Oak	S15°W	72.98'	Nail & tag 52" Oak	S15°W	73.11'
Nail & tag 36" Oak	S40°W	25.42'	Nail & tag 44" Oak	S40°W	25.22'
Nail & tag 16" Twin Oak	N85°W	51.29'	Nail & tag 24" Twin Oak	N85°W	51.08'
Nail & tag 18" Twin Oak	N20°W	74.11'	Nail & tag 26" Twin Oak	N20°W	74.20'
Nail & tag 12" Choke Cher.	N50°E	28.41'	Nail & tag 20" Choke Cher.	N50°E	28.35'
Nail & tag 12" Ash	N20°E	93.42'	Nail & tag 20" Walnut	N20°E	93.35'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 Standard Kent County Monument

Nail & KC Remon. tag E. side 52" Oak	S15°W	73.11'
Nail & KC Remon. tag E. side 44" Oak	S40°W	25.22'
Nail & KC Remon. tag N. side 24" Twin Oak	N85°W	51.08'
Nail & KC Remon. tag E. side 26" Twin Oak	N20°W	74.20'
Nail & KC Remon. tag SE side 20" Choke Cherry	N50°E	28.35'
Nail & KC Remon. tag SE side 20" Walnut	N20°E	93.35'

C/L Road 4' East; Fence line West



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN *Harry Hubers*

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995