

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>9W</u>	<u>F-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REG. OF DEEDS
97 APR 29 AM 8:22
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9830

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5	1830	GLO	Mullett	Set Post
	1973	LCRC #545	Spicer	"T" Iron
	1983	LCRC #3282	Hay	Set Kent County Monument
	1995	LCRC #8294	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by C. S. Hay on 3/25/83 and was recorded per LCRC #3282

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


F-5 Found standard Kent Co. Mon. (Harrison), per witnesses from above LCRC as set by C. S. Hay in place of the "T" Iron he found. Said "T" Iron checks with LCRC #545.

LCRC #3282	LCRC #8204
Nail & tag 12" Walnut N20°W 69.42'	Nail & tag MBT Pole N30°E 42.15'
Nail & tag MBT Pole N20°W 42.11'	Nail & tag 44" Maple S15°E 108.72'
Nail & tag 14" Oak N30°E 28.86'	Nail & tag 12" dbl. Elm N85°W 34.88'
Nail & tag 40" Maple S15°E 108.87'	Nail & tag 8" Maple S35°W 50.85'
Nail & tag 6" dbl. Elm N85°W 34.90'	Nail & tag 8" Poplar S85°E 26.90'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 Standard Kent County Monument	
Nail & KC Remon. tag W. side MBT Pole	N30°E 42.15'
Nail & KC Remon. tag W. side 44" Maple	S15°E 108.72'
Nail & KC Remon. tag E. side 8" Maple	S35°W 50.85'
Nail & KC Remon. tag S. side P. Pole	S85°E 34.00'
Capped Rerod (Nederveld)	N90°W 33.00'
C/L Asphalt Rd. is East 2' m/1	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077
P.A. 345 1990 KENT COUNTY

Date 3/27/97

PEER APPROVED 3/27/97
CHAIRMAN Harry Kubele