

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY
(County)

Located In: Corner Code #

- 1. Public Land Survey T 6N R 9W F-11
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

REG. OF DEEDS

Luci Spindel

97 APR 29 AM 8:22

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9833

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 9, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|------|------|---------------|------------|--------------------------------------|
| F-11 | 1830 | GLO | Mullett | Set Post |
| | 1964 | Kent Co. Wit. | | 1/2" Iron & Boat Spike |
| | 1979 | LCRC #1308 | Nederveld | 1" Round Iron in Mon. Box |
| | 1981 | LCRC #2257 | Merdzinski | Set Kent County Monument in Mon. Box |
| | 1995 | LCRC #8207 | Breitels | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 8/13/81 and was recorded per LCRC #2257

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #1308.

LCRC #2257

SW cor. school hse. N50°E 154.00' NW cor. fnd. house
 Nail & tag 36" Oak N25°W 61.00'
 Nail & tag P. Pole S25°W 63.30' S35°E 118.18'
 Nail & tag Fc. post N55°W 58.13'
 Nail & tag curb joint S70°W 44.08'

LCRC #8207

SW cor. school hse. N50°E 153.93'
 Nail & tag 42" Oak N25°W 60.88'
 Nail & tag P. Pole S25°W 63.46'
 NW cor. hse. fnd. S35°E 118.40'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Standard Kent County Monument

| | | |
|--------------------------------------|-------|---------|
| SW corner school house foundation | N50°E | 153.93' |
| Nail & KC Remon. tag NE side 42" Oak | N25°W | 60.88' |
| Nail & KC Remon. tag W. side P. Pole | S25°W | 63.46' |
| NW corner house foundation | S35°E | 118.40' |

On C/L North & South and East & West ±



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/27/97
 CHAIRMAN *Harry Kuberski*