

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	F-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 OCT 14 AM 10:01  
REG. OF DEEDS  
*Lucy Bond*

**10040**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on July 14, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-12 1830---GLO---Not Set
- 1944---Kent Co. Wits.---Iron  
26" Maple NW 43.75' 6" Maple NE 32.57'  
CP SW 53.35' C/L steel FP W 29.2'
- 1963-65---Williams & Works---Iron-Mon. Box
- 1983---LCRC #3661---Bonnema---2" Iron in Mon. Box  
C/L steel fc. post W 29.25' PP S30°W 53.90' 34" Maple N40°W 44.16'  
24" Maple N85°E 28.25' SE cor. stone on hse. S40°W 140.15'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- F-12 Found 2" Iron in Mon. Box per the following witnesses:  
C/L steel fc. post West 29.25'  
Fd. nail in 36" Maple N40°W 44.12'  
Fd. nail in 27" Maple N85°E 28.25'

2" Iron in Mon. Box is 2.3' N. and 2.1' E. of intersection of 1/4 lines and agrees with measurments of others.

The 2" Iron in Mon. Box is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- F-12 Set Standard Kent Co. Monument (Harrison) in Mon. Box in place of 2" Iron  
C/L steel fence post West 29.25'  
Nail & KC Remon. tag SE side P. Pole S35°W 54.65'  
Dbl. Head Nail S. side 27" Maple N85°E 28.25'  
Nail & KC Remon. tag E. side 36" Maple N40°W 44.12'  
Nail & KC Remon. tag NW side 10" Maple N35°E 48.97'  
In C/L N-S Asph. Rd. ± and occupation lines E-W



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/24/97

CHAIRMAN *Harry Hubert*