

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 6N R 9W	G-3
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 APR 29 AM 8:22
 REG. OF DEEDS
Lucy Spauld

9837
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-3	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Leaded Stone
1973		LCRC #466	Spicer	1" Iron
1974		LCRC #646	Vankooten	3/4" Iron
1981		LCRC #2724	Merdzinski	Set Kent County Monument
1995		LCRC #8210	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12/30/81 and was recorded per LCRC #2724

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC's #466 & #646.

<u>LCRC #2724</u>		<u>LCRC #8210</u>	
Nail & tag 18" Maple	N25°W 7.25'	Nail & tag 24" Maple	N25°W 7.28'
Nail & tag 20" Ash	N85°W 24.47'	Nail & tag 24" Ash	N85°W 24.58'
Nail & tag 8" Cherry	S45°E 8.83'	Nail & tag 12" Cherry	S45°E 8.85'
Nail & tag 6" Ash	N05°E 22.92'	Nail & tag 12" Ash	N05°E 22.99'
Nail & tag 44" Oak	S25°W 22.37'	Nail & tag 50" Oak	S25°W 22.41'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>G-3 Standard Kent County Monument</u>	
Nail & KC Remon. tag E. side 24" Maple	N25°W 7.28'
Nail & KC Remon. tag S. side 24" Ash	N85°W 24.58'
Nail & KC Remon. tag W. side 12" Cherry	S45°E 8.85'
Nail & KC Remon. tag W. side 12" Ash	N05°E 22.99'
Nail & KC Remon. tag W. side 50" Oak	S25°W 22.41'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/27/97
 CHAIRMAN *Harry [Signature]*