

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in
KENT COUNTY

Located In:	Corner Code #
T 6N R 9W	G-8
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

REG. OF DEEDS
97 APR 29 AM 8:22
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
9842
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8	1830	GLO	Mullett	Set Post
	1957	Kent Co. Wit.		Stone
	1973	LCRC #602	VanKooten	1" Iron in mon. box
	1981	LCRC #2259	Bueche	Set Kent County Monument
	1995	LCRC #8215	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6/19/81 and was recorded per LCRC #2259.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Iron he found inside a mon. box. Said Iron checks with LCRC #602.

LCRC #2259	LCRC #8215	"X" on curb	N55°W 40.20'
"X" on conc. curb	"X" on curb	S50°W	40.40'
"X" on conc. curb	Nail & tag 10" dead Maple	S30°W	55.78'
Nail & tag 10" Maple	Nail & tag 40" Maple	N85°W	82.41'
Nail & tag 36" Maple	Nail & tag 12" Elm	N25°E	87.78'
N. edge N. leg sign post East	N. edge N. leg sign post	N90°E	27.14'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 Standard Kent County Monument	N55°W	40.20'
"X" on conc. curb	S50°W	40.40'
"X" on conc. curb	N65°W	82.41'
Nail & KC Remon. tag S. root 40" Maple	N25°E	87.78'
Nail & KC Remon. tag W. side 12" Elm	N90°E	27.14'
N. edge of N. leg of sign post		
On C/L blktp. road N & S		
4' m/l North of C/L gravel road West		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077
P.A. 345 1990 KENT COUNTY

Date 3/27/97

PEER APPROVED 3/27/97
CHAIRMAN Farm Huber