

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	<u>G-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:23
REG. OF DEEDS
Lucy Hand

9843

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 10, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-9	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Bolt
	1971	LCRC #41	Chambers	Bolt
	1981	LCRC #2375	Bueche	Set Kent County Monument
	1995	LCRC #8216	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/25/81 and was recorded per LCRC #2375.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1 1/4" x 6" Pipe over top of 1" x 24" solid rod he found. Both check with Kent Co. Wit. & LCRC #41.

LCRC #2375		LCRC #8216	
"X" cut curb return	S45°E 46.15'	NE cor. fnd. to bldg.	S65°W 149.83'
NE cor. fnd. to bldg.	S65°W 149.83'	SE cor. fnd. to hse.	N45°E 159.85'
SE cor. fnd. to house	N25°W 91.61'	Nail & tag Guy Pole	N50°W 65.62'
SE cor. fnd. to house	N45°E 159.85'	Nail & tag CP Pole	N50°E 66.05'
		Nail & tag CP Pole	S50°E 81.90'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 Standard Kent County Monument	
NE cor. foundation to bldg.	S65°W 149.83'
SE cor. foundation to house	N45°E 159.85'
Nail & KC Remon. tag SW side Guy Pole	N50°W 65.62'
Nail & KC Remon. tag NW side CP Pole	N50°E 66.48'
Nail & KC Remon. tag NE side CP Pole	S50°E 81.90'
C/L blktp. E & W is North 2.1'	
On C/L blktp. N & S	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97