

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 6N R 9W	G-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REG. OF DEEDS

Lucy Bond

97 APR 29 AM 8:23

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9847

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1973	LCRC #942	Spicer	3/4" Iron
	1981	LCRC #1697	Merdzinski	Set Kent County Monument
	1995	LCRC #8220	Breitels	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/24/81 and was recorded per LCRC #1697

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #942.

<u>LCRC #1697</u>	SE cor. hdwll.	N10°W	58.81'	<u>LCRC #8220</u>	SE cor. hdwll.	N10°W	58.78'
Nail & tag 14" Maple		N35°W	61.65'	Nail & tag 20" Maple		N35°W	61.60'
Nail & tag MBT/CP Pole		N75°E	80.79'	Nail & tag CP Pole		N75°E	80.82'
Nail & tag 12" Hickory		S80°W	122.20'	Nail & tag 12" Ash		S10°W	102.35'
Nail & tag 12" Maple		S05°W	134.63'	Nail & tag 10" Hickory		S80°W	88.22'
Iron - East	66.00'			KC Mon. (G-1, 5-9)	East	66.00'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Standard Kent County Monument			
Nail & KC Remon. tag W. side	20" Maple	N35°W	61.60'
Nail & KC Remon. tag N. side	CP Pole	N75°E	80.82'
Nail & KC Remon. tag E. side	12" Ash	S10°W	102.35'
Nail & KC Remon. tag N. side	10" Hickory	S80°W	88.22'
SE corner of headwall		N10°W	58.78'
Kent Co. Mon. at G-1, T5N, R9W		East	66.00'
On C/L E-W bit. road and 30'± West of N-S bit. road			



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Frank Kulesc*