

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	H-7
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:23
REG. OF DEEDS
Eric Standa

9851

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Mar. 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		No. desc. - wits given
1978	LCRC #1211	Jonker	"X" on stone	
1979	LCRC #1246	Merdzinski	"X" on stone	
1981	LCRC #2223	Jonker	Set Kent County Monument	
1990	LCRC #5469	Starr	Kent County Monument in gravel drive	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10/30/81 and was recorded per LCRC #2223

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Stone with "X" cut he found. Said Stone checks with LCRC's #1211 & #1246.

LCRC #2223				LCRC #5469			
Remon. tag 40" Oak	N26°W	35.07'	Nail & tag 40" Oak	N26°W	35.07'		
Remon. tag 8" Walnut	N88°W	36.27'	Nail & tag 8" Walnut	N88°W	36.27'		
Remon. tag 10" Walnut	N75°E	87.05'	Nail & tag 10" Walnut	N75°E	87.05'		
NW cor. house (frame)	S21°E	49.68'	NW cor. house (frame)	S21°E	49.74'		
NE cor. house (frame)	S48°E	79.17'	NE cor. house (frame)	S48°E	79.19'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Standard Kent County Monument in asphalt drive

Nail & KC Remon. tag N. side 12" Walnut	N88°W	36.15'
Nail & KC Remon. tag N.xx side 16" Walnut	N75°E	87.10'
NW corner house (newer siding)	S21°E	49.52'
NE corner house (newer siding)	S48°E	79.19'
NW corner garage (siding)	S90°W	36.68'
NE corner garage (siding)	S25°W	26.80'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Puhar*