

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|--------------|-------------|
| 1. Public Land Survey | T <u>6</u> N | R <u>9</u> W | H- <u>9</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:23
REG. OF DEEDS
Luc Standa

9852

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|------------------|--------------|--------------------------|
| H-9 | 1830 | GLO | Mullett | Set Post |
| | 1908 | Williams & Works | | Stone & Bolt |
| | | Kent Co. Wit. | | Iron Bolt |
| | 1983 | LCRC #3566 | Chettleburgh | Set Kent County Monument |
| | 1990 | LCRC #5470 | Starr | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 10-24-83 and was recorded per LCRC #3566.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


H-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh in place of the RR Spike he found. Said RR spike checks with Williams & Works information and Kent Co. Wit.

- | | | | |
|-------------------|-------------|-----------------------|---------------|
| <u>LCRC #3566</u> | | <u>LCRC #5470</u> | |
| Nail in 4" Elm | NNE 55.94' | Nail & tag 33" Maple | S55°E 49.90' |
| Nail in 33" Maple | SE 49.88' | Nail & tag 28" Maple | S40°W 36.86' |
| Nail in 28" Maple | SW 37.02' | Nail & tag 32" Maple | S80°W 148.68' |
| Nail in 32" Maple | WSW 148.63' | Nail & tag 6" Elm | N45°W 67.97' |
| | | Nail & tag Tw. 6" Elm | North 50.27' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|-----|---|-------|--------|
| H-9 | Standard Kent County Monument | | |
| | Nail & KC Remon. tag NE side 36" Maple | S55°E | 49.90' |
| | Nail & KC Remon. tag SE side 32" Maple | S40°W | 36.75' |
| | Nail & KC Remon. tag E. side Tw. 8" dead tree | N45°W | 68.00' |
| | Nail & KC Remon. tag E. side Tw. 8" Elm | North | 50.34' |
| | Nail & KC Remon. tag E. side 10" Elm | N20°E | 51.41' |
| | C/L E-W bit. road is 2'± North | | |
| | On fence & tree row South | | |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Kubers*