

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey

T6N R9W I-9

T	R	
T	R	
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:23  
REG. OF DEEDS  
*Lucy Spauld*

9860

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-9	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Hole in pavement
	1959	MDSH		Hole in pavement
	1983	LCRC #3565	Chettleburgh	Set Kent County Monument
	1990	LCRC #5480	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 10/24/83 and was recorded per LCRC #3565.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh at the location of the Hole in Pavement he found. Said Hole in Pavement checks with Kent Co. Wit. and MDSH information.

<u>LCRC #3565</u>		<u>LCRC #5480</u>	
Nail in Power Pole	SW 53.70'	Nail & tag P. Pole	S45°W 53.70'
Nail in 7" Elm	NW 95.69'	Nail & tag 7" Elm	N55°W 95.78'
"X" on top of rock	N 59.26'	"X" on tip of rock	North 59.26'
Nail in Power Pole	ESE 257.05'	Nail & tag P. Pole	S80°E 257.05'
		Nail & tag 4" Elm	South 43.52'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Standard Kent County Monument

Nail & KC Remon. tag NW side new P. Pole	S45°W	52.71'
Nail & KC Remon. tag SW side 10" stump	N55°W	95.78'
Nail & KC Remon. tag N. side new P. Pole	S80°W	327.47'
Nail & KC Remon. tag N. side new P. Pole	S80°E	259.90'
Cut "X" top concrete culvert	N55°W	65.47'
C/L East and West Bit. road is North 5.7' ±		
On tree row North		



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN Harry Hubert