

03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 9W I-10

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:23
REG. OF DEEDS
9861
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27	●	26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10	1830	GLO	Mullett	Set Post
	1909	Williams & Works		Cor. at mid-mile per dim.
		Kent Co. Wit.		Cor. at mid-mile per dim.
	1983	LCRC #3547		Set Kent County Monument by single proportionate measurement
	1990	LCRC #5481	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas Chettleburgh on 10-11-83 and was recorded LCRC #3547

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas Chettleburgh.

LCRC #3547

LCRC #5481

Nail in 22" Oak	N	44.43'	Nail & tag 22" Oak	North	44.43'
Nail in 17" Beech	NE	53.58'	Nail & tag 17" Beech	N35°E	53.58'
Nail in 17" Beech	E	51.18'	Nail & tag 17" Beech	East	51.18'
Nail in 14" Beech	SE	28.17'	Nail & tag 14" Beech	S45°E	28.17'
Nail in 19" Beech	S	46.61'	Nail & tag 19" Beech	South	46.61'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard Kent County Monument

Nail & KC Remon. tag W. side	26" Oak	North	44.43'
Nail & KC Remon. tag SE side	24" Beech	N35°E	53.61'
Nail & KC Remon. tag S. side	24" Beech	East	51.21'
Nail & KC Remon. tag SW side	18" Beech	S45°E	28.17'
Nail & KC Remon. tag W. side	24" Beech	South	46.61'
200'± North of North ROW fence of I-96			
On West edge of woods			



Signed by

Kirk Breitels

Date

3/27/97

Surveyor's Michigan License No.

30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED

3/27/97

CHAIRMAN

Harry Kuper