

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

97 APR 29 AM 8:24

**SECTION**

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6N</u> R <u>9W</u>	I-11
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

*Luigi Bond*  
REG. OF DEEDS

**9862**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11	1830	GLO	Mullett	Set Post
	1959	Kent Co. Wit.		1/2" Iron
	1982	LCRC #2888	Jonker	1/2" Rerod
	1982	LCRC #3088	Jonker	Set Kent County Monument
	1990	LCRC #5482	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-15-82 and was recorded per LCRC #3088.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Rerod he found. Said Rerod checks with Kent Co. Wit. and LCRC #2888.

LCRC #3088

Remon. tag 32" Oak	N25°E	35.45'
Remon. tag 10" Elm	S65°E	65.76'
Remon. tag 5" Elm	S40°W	32.66'
Remon. tag 32" Maple	N65°E	72.59'

LCRC #5482

Nail & tag 32" Oak	N25°E	35.45'
Nail & tag 32" Maple	N65°E	72.59'
Nail & tag 8" Poplar	S40°E	36.78'
Nail & tag 8" Elm	N05°W	28.91'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Standard Kent County Monument

Nail & KC Remon. tag E. side 36" Oak	N25°E	35.45'
Nail & KC Remon. tag SE side 36" Maple	N65°E	72.68'
Nail & KC Remon. tag SW side 16" Poplar	S40°E	36.64'
Nail & KC Remon. tag E. side 12" Cherry	N05°W	37.42'
On C/L E-W bit. road		
On N-S tree row and on fence line North		



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/27/97  
CHAIRMAN *Harry Hubert*