

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 97 APR 29 AM 8:26  
*Lucy J. Bond*  
 REG. OF DEEDS

For corners in **SECTION**  
**KENT COUNTY**

Located In:	Corner Code #
1. Public Land Survey	T 6N R 9W I-12
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

**9863**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1830	GLO	Mullett	Set Post
	1982	LCRC #2888	Jonker	1" Sq. Iron
	1982	LCRC #3089	Jonker	Set Kent County Monument
	1990	LCRC #5483	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/17/82 and was recorded per LCRC #3089.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" Sq. Iron he found. Said Iron checks with LCRC #2888.

LCRC # \_\_\_\_\_ LCRC #5483  
 Remon. tag 10" Maple S65°E 52.95' same witnesses as LCRC #3089

Remon. tag 16" Beech S15°W 46.20'

Remon. tag 8" Maple S80°W 28.16'

Remon. tag 28" Nut tree N00°E 8.8'

At 4 way fence corner

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Standard Kent County Monument

Nail & KC Remon. tag N. side 15" Maple S65°E 52.77'

Nail & KC Remon. tag E. side 20" Beech S15°W 46.07'

Nail & KC Remon. tag S. side 12" Maple S80°W 28.10'

Nail & KC Remon. tag E. side 30" Nut Tree N00°E 8.83'

Newer E-W fence is South 1'



Signed by Kirk Breitels

Date 3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN Harry Hubert