

MAR 03 1998

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 6N R 9W J-3
- T R
- T R
- T R
- T R
- 2. Property Controlling S T R
- In Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3	1830	GLO	Mullett	Set Post
	1985	LCRC #4492	VanKooten	Rerod
	1991	LCRC #5857	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6-13-91 and was recorded per LCRC #5857.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Rerod he found over a second Rerod. Both Rerods checks with LCRC #4492.

LCRC #5857

Center W. gate post @ base	S80°E	57.90'
MSHD tag & nail SE side old P. Pole	N40°E	66.88'
PK Nail S. side P. Pole	N70°W	127.99'
PK Nail S. side P. Pole	N70°E	127.14'

On asphalt road to fairgrounds, 2' North of South edge

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 Standard Kent County Monument

Center W. gate post @ base	S80°E	57.85'
MSHD tag & nail SE side old P. Pole	N40°E	66.78'
PK Nail S. side P. Pole	N70°W	127.99'
PK Nail S. side P. Pole	N70°E	127.14'
Nail & KC Remon. tag NW side new P. Pole	N40°E	65.25'

On asphalt road to fairgrounds, 2' North of South edge

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 APR 29 AM 8:24
 REG. OF DEEDS

9865

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Signed by Kirk Breitels
 Surveyor's Michigan License No. 30077

Date 3/27/97



P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/27/97
 CHAIRMAN Harry Kubes