

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located in: Corner Code #

- | | | |
|------------------------------------|-----------|-----|
| 1. Public Land Survey | T 6N R 9W | J-4 |
| | T R | |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Kirk Breitels, in a field survey on Sept. 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Register of Deeds Stamp & File Number

REG. OF DEEDS
97 NOV 13 PM 1:01
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORDS

10272

A. Description of original monument and accessories and/or subsequent restoration:

- J-4 1830---GLO---Not Set
1953 & 1959---Williams & Works---Surveys SW 1/4 & NE 1/4 of Sec. 11
Kent Co. Wits.---No information
1977-81---Surveys---Nederveld---"T" Iron
8" Elm E 21.78' 12" dbl. Box Elder SSW 6.17'
NE cor. bldg. W 10' 8" Sassafras SE 49.64'
1985---LCRC #4492---VanKooten---"Set true center of Sec. 11"
16" Elm WSW 18.87' 14" Box Elder ESE 8.70' Fc. Post NNE 42.8'
Service Pole SSW 56.92' Iron Pipe E 10.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-4 Found Capped Rerod (MVK) per LCRC #4492 - at "True center" ±
Found "T" Iron per Nederveld witnesses - determined to be lot corner in the "Village of Segwun" (Liber 1, Pg. 45)
Found Irons - "1/8 corners" - and other Irons in the SW 1/4 and NE 1/4 per 1953 & 1959 Williams & Works surveys. Also found Irons in the SE 1/4 that coincide with either the Capped Rerod per LCRC #4492 or the "T" Iron per Nederveld.
Peer Group determined that no C 1/4 corner (J-4) is necessary (surrounded by the "Village of Segwun"), that the "1/8 corner" Irons found per 1953 & 1959 Williams & Works surveys have historically controlled property location South of the Grand River and outside of the "Village of Segwun."

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-4 NO MONUMENT SET AT THIS CORNER

See LCRC # 10273 and LCRC # 10274 for location of property controlling corners.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/25/97
CHAIRMAN Humphreys



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 10/30/97